

**SECTION 1150 - REPLACEMENT OF EXISTING MAIL BOXES, CULVERTS, CLOTHES LINES & POSTS, FENCES, DRAIN TILE, AND OTHER SUCH FACILITIES**

**PART 1 - GENERAL**

**1.1 SCOPE OF WORK:**

Provide all labor, materials, equipment and services required for replacement of existing mail boxes, culverts, clothes lines & posts, fences, drain tile, and other such facilities when they are molested or disturbed during the work as specified herein. Such facilities shall only be removed for construction as designated or approved by the ENGINEER.

**PART 2 - EXECUTION**

Existing mail boxes, drainage culverts, clothes lines & posts, fences, drain tile, and other such facilities inside or outside the construction limits shall not be molested or disturbed unless indicated on the plans or necessary as approved by the ENGINEER. When such facilities are removed or damaged (whether approved or not), they shall be replaced in at least as good a condition as found, as quickly as possible. Existing materials may be reused in replacing such facilities when materials have not been damaged by the CONTRACTOR's operations. Existing facilities damaged by CONTRACTOR's operation shall be replaced with new materials of the same type and quality (unless otherwise indicated on the plans) at the CONTRACTOR's expense. Drainage culverts and drain tile shall be installed in accordance with the applicable sections of O.D.O.T. specification Item 603.

Replacement of paved drainage ditches within highway right-of-way shall be accomplished in accordance with Ohio Department of Transportation Specifications.

**PART 3 - BASIS OF PAYMENT:**

Work performed under this item shall be at the CONTRACTOR'S expense and is not a pay item unless specific bid items are included on the proposal forms.

END OF SECTION